



Project: Central Avenue Bridge

Slab Strengthening




Location: Burlington, IA



Description of Work

The unique “X-shape” bridge lacked sufficient top and bottom rebar due to a shop drawing error. Both positive and negative bending capacities needed to be increased at certain regions of the bridge slab.

The carbon-based Tyfo[®] SCH-41 Composite System was utilized on the bottom side of the slab to strengthen areas lacking positive moment reinforcement. For negative bending strengthening, the Tyfo[®] UC carbon plates were inserted into saw cuts on the topside of the slab. The Tyfo[®] S high-strength epoxy was filled into the saw cuts around the plates and fine gravel was adhered at the top surface. The bridge slab was strengthened by creative, non-obtrusive methods with the Tyfo[®] Composite Systems.



Fibrwrap Construction Inc.

4255 E. Airport Drive, Ontario, CA 91761

Tel: 909.390.4363 | Fax: 909.390.7030 | Email: info@fibrwrapconstruction.com

www.fibrwrapconstruction.com

Contractor's Li. 621404